

ENRON

OIL & GAS COMPANY

P.O. BOX 1815, VERNAL, UTAH 84078 (801)789-0790

RECEIVED

JUN 04 1993

June 1, 1993

DIVISION OF
OIL GAS & MINING

Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

RE: NOTICE OF STAKING
CHAPITA WELLS UNIT 338-13
Sec. 13, T9S, R22E
Uintah County, Utah
Lease No. U-0282

Dear Mr. Forsman:

Attached is a Notice of Staking on the subject well.

If you require further information, please contact this office.

Very truly yours,
ENRON OIL & GAS COMPANY

George McBride by J. D.

George McBride
Sr. Production Foreman

Attachment

cc: Division of Oil Gas & Mining
Doug Weaver/Toni Miller
Curt Parsons
File

/lw
NOSLTR

NOTICE OF STAKING

(Not to be used in place of
Application to Drill Form 9-331-C)

RMOGA
5/5/82

5. Lease Number

U-0282

1. Oil Well Gas Well X Other

6. If Indian, Allottee or Tribe Name

2. Name of Operator

Enron Oil & Gas Company

7. Unit Agreement Name

Chapita Wells Unit

3. Address of Operator or Agent

P. O. Box 1815, Vernal, Utah 84078

8. Farm or Lease Name

Chapita Wells Unit

4. Surface Location of Well

(Governmental 1/4 or 1/4 1/4)

1983' FSL & 829' FEL NE/SE

9. Well No.

338-13

10. Field or Wildcat Name

CWU/Wasatch

Attach: Topographical or other acceptable map

Showing location, access road, and lease boundaries

11. Sec., T., R., M., or

Blk and Survey or Area

Sec. 13 T9S, R22E

14. Formation Objective(s)

Wasatch

15. Estimated Well Depth

7400'

12. County or Parish

Uintah

13. State

Utah

16. To Be Completed by Operator Prior to Onsite

a. Location must staked - Completed

b. Access Road Flagged - Completed

c. Sketch and/or map of location, showing road, pad dimensions, reserve pit, cuts, and fills
(To be provided at onsite)

17. To Be Considered By Operators Prior to Onsite

a. H2S Potential - NA

b. Private Surface Ownership - NA

c. Cultural Resources (Archaeology) - Completed

d. Federal Right of Way

18. Additional Information

19. Signed Linda L. Wall Title Sr. Admin. Clerk

Date 06/02/93



TOPOGRAPHIC

MAP "B"

SCALE: 1" = 2000'

DATE 1-8-92



ENRON OIL & GAS CO.

CWU #338-13

SECTION 13, T9S, R22E, S.L.B.&M.

ENRON

OIL & GAS COMPANY

P.O. BOX 1815, VERNAL, UTAH 84078 (801)789-0790

June 23, 1993

Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

RE: APPLICATION FOR PERMIT TO DRILL
CHAPITA WELLS UNIT 338-13
SECTION 13, T9S, R22E
UINTAH COUNTY, UTAH
LEASE NO. U-0282


Dear Mr. Forsman:

Enclosed are the original and two (2) copies of the Application for Permit to Drill and associated attachments for the referenced well.

If further information is required regarding this matter, please contact this office.

Sincerely,

ENRON OIL & GAS COMPANY



George R. McBride
Sr. Production Foreman

Attachments

cc: State Division of Oil, Gas & Mining
D. Weaver/T. Miller
Suzanne Saldivar
File

RECEIVED

JUL 06 1993

DIVISION OF
OIL GAS & MINING

/lw
CWU338-13APD

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☐

GAS
WELL ☒

OTHER

SINGLE
ZONE ☐

MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

ENRON OIL & GAS COMPANY

3. ADDRESS OF OPERATOR

P.O. BOX 1815, VERNAL, UTAH 84078

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)
At surface

1983' FSL & 829' FEL NE/SE
At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

19.4 MILES SOUTHEAST OF OURAY, UTAH

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

829' ±

16. NO. OF ACRES IN LEASE

2440

17. NO. OF ACRES ASSIGNED
TO THIS WELL

80

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

1740' ±

19. PROPOSED DEPTH

7000'

20. ROTARY OR CABLE TOOLS

ROTARY

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4938' GRADED GROUND

22. APPROX. DATE WORK WILL START*

AUGUST 1993

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24.0#	240'	125 SX CLASS "G" + 2% CaCl ₂
7 7/8"	4 1/2"	10.5#	7000'	+ 1/2 #/SX CELLOFLAKE. 50/50
				POZMIX + 2% GEL + 10% SALT
				TO 400' ABOVE ALL ZONES
				OF INTEREST (+ 10% EXCESS).
				LIGHT CEMENT (11 PPG±)
				+ LCM TO 200' ABOVE OIL
				SHALE OR FRESH WATER
				INTERVALS (+ 5% EXCESS).

SEE ATTACHMENTS FOR:

8 POINT PLAN
DRILLING PROGRAM
BOP SCHEMATIC
SURFACE USE AND OPERATING PLAN
LOCATION PLAT
LOCATION LAYOUT
TOPOGRAPHIC MAPS "A", "B", AND "C"
GAS SALES PIPELINE EXHIBIT "A"
WELLSITE SCHEMATIC

JUL 08 1993

DIVISION OF
OIL, GAS & MINING

ENRON OIL & GAS COMPANY WILL BE THE
DESIGNATED OPERATOR OF THE SUBJECT
WELL UNDER NATION WIDE BOND #81307603.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Linda L. Hall TITLE SR ADMIN. APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
PERMIT NO. 43-047-30434 APPROVAL DATE 7-12-93
DATE 7-12-93
BY [Signature]
WELL SPACING: 649-2-3
APPROVED BY _____ TITLE _____
CONDITIONS OF APPROVAL, IF ANY:



T9S, R22E, S.L.B.&M.

ENRON OIL & GAS CO.

Well location, CWU #338-13, located as shown in the NE 1/4 SE 1/4 of Section 13, T9S, R22E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION AT THE SE CORNER OF SECTION 13, T9S, R22E, S.L.B.&M. TAKEN FROM THE RED WASH SW QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4989 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

STATE OF UTAH
COUNTY OF UTAH
REGISTERED LAND SURVEYOR
REGISTRATION NO. 5709
ROBERT J. HARRIS
DATE: 1-8-92

UINTAH ENGINEERING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(801) 789-1017

▲ = SECTION CORNERS LOCATED. (Brass Caps)

SCALE 1" = 1000'	DATE 1-8-92
PARTY D.A. J.F. T.D.H.	REFERENCES G.L.O. PLAT
WEATHER COLD	FILE ENRON OIL & GAS CO.

EIGHT POINT PLAN

CHAPITA WELLS UNIT 338-13

SECTION 13, T9S, R22E

UINTAH COUNTY, UTAH

RECEIVED

JUL 08 1993

DIVISION OF
OIL GAS & MINING

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS & WATER ZONES:

FORMATIONS	DEPTH	TYPE ZONES	MAXIMUM PRESSURE
Green River			
Oil Shale	1,751'		
"H" Marker	3,190'		
"J" Marker	3,854'		
Base "M" Marker	4,414'		
Wasatch			
Peters Point	4,802'	Gas	2,200 PSI
Chapita Wells	5,332'	Gas	2,400 PSI
Buck Canyon	5,892'	Gas	2,700 PSI
Island	6,815'		
EST. TD	7,000'	Anticipated BHP	3,200 PSI

All depths are based on estimated KB elevation 4,950'. Maximum pressure estimates are based on bottom hole pressures measured on offset or near vicinity wells to the subject well.

3. PRESSURE CONTROL EQUIPMENT: BOP Schematic Diagram attached.

4. CASING PROGRAM:

<u>HOLE SIZE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>GRADE</u>	<u>MINIMUM SAFETY FACTOR</u>		
						<u>COLLAPSE</u>	<u>BURST</u>	<u>TENSILE</u>
12 1/4"	0' - 240'	240'	8 5/8"	24.0#	J-55 ST&C	1370 PSI	2950 PSI	263,000#
7 7/8"	0' - 7000'	7000'	4 1/2"	10.5#	J-55 ST&C	4010 PSI	4790 PSI	146,000#

All casing to be used will be new or inspected.

5. MUD PROGRAM:

<u>INTERVAL</u>	<u>MUD TYPE</u>
0' - 240'	Air
240' - 4000'	Air/Mist & Aerated Water
4000' - TD	Air/3% KCl water or KCl substitute
TD	Gel/polyacrylamide polymer w/5-10% LCM

RECEIVED

JUL 08 1993

EIGHT POINT PLAN

CHAPITA WELLS UNIT 338-13

PAGE NO. 2

DIVISION OF
OIL GAS & MINING

Lost circulation probable from 1500' to 3000'±.
Sufficient mud inventory will be maintained on location during drilling to handle any adverse conditions that may arise.

6. VARIANCE REQUESTS:

- A. Enron requests a variance to regulations requiring a straight run blooie line. (Where possible a straight run blooie line will be used, and where it is not possible two targeted tees will be used).
- B. Enron requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line. (Not required on aerated water system).
- C. Enron requests a variance to regulations requiring the flare pit to be located down wind of the prevailing wind direction, which is not possible on the CWU 338-13 location due to topography..

7. EVALUATION PROGRAM:

Logs:	Dual Laterolog/GR	From base of surface casing to TD.
	FDC-CNL/GR/Caliper	TD to 3100'.
	Linear 2" DLL.	

Cores: None Programmed.
DST' : None Programmed.

Completion: To be submitted at a later date.

8. ABNORMAL CONDITIONS:

None anticipated.

9. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

Attachment: BOP Schematic Diagram

RECEIVED

JUL 08 1993

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

DIVISION OF
OIL, GAS & MINING

Company/Operator: ENRON OIL & GAS COMPANY
Well Name & Number: CHAPITA WELLS UNIT 338-13
Lease Number: U-0282
Location: 1983' FSL & 829' FEL NE/SE Sec. 13 T. 9S R. 22E
Surface Ownership: FEDERAL LANDS - BLM

NOTIFICATION REQUIREMENTS

- Location Construction - forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and related Equipment Tests - twenty-four (24) hours prior to running casing and tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

THIRTEEN POINT SURFACE USE PROGRAM

1. EXISTING ROADS

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing road.
- B. The proposed well site is located approximately 19.4 miles southeast of Ouray, Utah - See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary. No off lease Right-of-Way will be required.

2. PLANNED ACCESS ROAD

- A. The access road will be 0.3 mile in length. See attached TOPO Map "B".
- B. The access road has a 30 foot ROW w/18 foot running surface.
- C. Maximum grade on access road will be 5%.
- D. No turn outs will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No culverts, bridges or major cuts & fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards or fences will be required or encountered.

New or reconstructed roads will be centerline - flagged at time of location staking.

All travel will be confined to existing access road Right-of-Way. Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service Publication: Surface Operating Standards For Oil & Gas Exploration and Development, (1989).

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, drainage, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot Right-of-Way will not be allowed.

Road drainage crossing shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

No Right-of-Way applications will be required.

As operator Enron Oil & Gas Company shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

3. LOCATION OF EXISTING WELLS WITHIN A ONE MILE RADIUS OF PROPOSED WELL LOCATION

- A. Water wells - None.
- B. Abandoned wells - None
- C. Temporarily abandoned wells - None
- D. Disposal wells - None
- E. Drilling wells - None
- F. Producing wells - Seven - See attached TOPO Map "C" for location of producing wells.
- G. Shut in wells - None
- H. Injection wells - None

4. LOCATION OF EXISTING/AND OR PROPOSED FACILITIES

A. ON WELL PAD

- 1. Tank batteries - None
- 2. Production facilities will be set on location if well is successfully completed for production. Facilities will consist of well head & valves, separator, dehy, 210 BBL condensate tank, meter house and attaching piping. See attached facility diagram.
- 3. Oil gathering lines - None
- 4. A 3 1/2" gathering line will be buried from dehy to north end of location.
- 5. Injection lines - None
- 6. Disposal lines - None
- 7. Surface pits - None

B. OFF WELL PAD

- 1. Proposed location of attendant off pad gas flowlines shall be flagged prior to archaeological clearance.
- 2. A 4 1/2" OD steel above ground natural gas pipeline will be laid approximately 2200'± from proposed location to a point in the NE/SW of Sec. 13, T9S, R22E where it will tie into Questar Pipeline Co.s' existing line. Proposed pipeline crosses BLM administered lands within the Chapita Wells Unit, thus no Right-of-Way grant will be required. See attached Exhibit A showing pipeline route.
- 3. Proposed gas gathering pipeline will be a 4 1/2" OD steel, welded line laid on the surface.
- 4. Protective measures and devices for livestock and wildlife will be taken and or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire content of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

The production facilities will be placed on the east side of location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities required will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Carlsbad Canyon.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate rental or other financial obligation as determined by the authorized officer.

5. LOCATION & TYPE OF WATER SUPPLY

- A. Water supply will be from Ouray Brine Plant at Ouray, Utah, and/or Target Trucking Inc.'s' water source in the SW/SW Sec. 35, T9S, R22E, Uintah County, Utah (State water right #49-1501).
- B. Water will be hauled by Target Trucking Inc.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIAL

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of location.
- B. All construction material will come from Federal Land.
- C. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at an approved waste disposal facility.
- 4. Produced waste water will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. During the 90 days period, an application for approval of a permanent disposal method and location, together with the required water analysis, will be submitted for the AO's approval.
- 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on drilling rig to avoid leakage of oil to pit.

- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in reserve pit or be removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to reserve pit will be avoided by flaring them off in flare pit at time of recovery.

Burning will not be allowed. all trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

On BLM administered land:

The reserve pit will be constructed so as not to leak, break, or allow discharge. The reserve pit shall be lined.

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

8. ANCILLARY FACILITIES

- A. No airstrips or camps are planned for this well.

9. WELL SITE LAYOUT

- A. Refer to attached well site plat for related topography cuts and fills & cross sections.
B. Refer to attached well site plat for rig layout and soil material stockpile location as approve on On-site.
C. Refer to attached well site plat for rig orientation parking areas, and access road.

The reserve pit will be located on the west side of location.

The flare pit will be located downwind of the prevailing wind direction on the northwest side of location a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled topsoil will be stored on the south end.

Access to the well pad will be from the south.

- NA Diversion ditch(es) shall be construct on the _____ side of the location (above/below) the cut slope, draining to the _____
NA Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location between the _____
NA The drainage(s) shall be diverted around the side(s) of the well pad location.
NA The reserve pit and/or pad locations shall be constructed long and narrow for topographic reasons _____.

— The southeast corner of the well pad will be rounded off to avoid the drainage.

FENCING REQUIREMENTS

All pits will be fenced according to the following minimum standards:

- A. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total eight of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16'.
- E. All wire shall be stretched by using a stretching device before is be attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguards (shall/shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RESTORATION OF SURFACE

A. PRODUCING LOCATION

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 12 months from the date of well completion. Before any dirt work takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc., will be removed.

Contact appropriate surface management agency for required seed mixture.

B. DRY HOLE/ABANDONED LOCATION

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP

Access road: Federal
Location: Federal

12. OTHER INFORMATION

- A. Enron Oil & Gas Company will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the AO. Within five working days the AO will inform the operator as to:

-whether the materials appear eligible for the National Register of historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used.

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

-if the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guideline for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator Enron Oil & Gas Company will control noxious weeds along Right-of-Ways for roads, pipelines, well sites or other applicable facilities. A list of noxious weeds will be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

- C. Drilling rigs and/or equipment used during drilling operations on this wellsite will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for for stacking and storing drilling rigs.)

Additional Surface Stipulations

- _____ No construction or drilling activities shall be conducted between May 15 and June 20 because of antelope kidding.
- NA No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.
- NA No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.
- NA There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).
- NA No cottonwood trees will be removed or damaged.
- _____ Pond will be constructed according to BLM specifications approximately 300 ft. south of the location, as flagged on onsite.

LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION

Enron Oil and Gas Company
P.O. Box 1815
Vernal, Utah 84078
George McBride
Telephone: (801) 789-0790

Enron Oil and Gas Company
P.O. Box 250
Big Piney, Wyoming
Jim Schaefer
Telephone: (307) 276-3331

All lease/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approval plan of operations, and any applicable Notice to Lessees. Enron Oil & Gas Company is fully responsible for the actions of their subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

A copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities


The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in the Plan are to the best of my knowledge, true and correct; and that the work associated with the operations proposed here in will be performed by ENRON OIL & GAS COMPANY and its contractors and sub-contractors in conformity with this Plan and the terms and conditions under which it is approved.

6/23/93

DATE




GEORGE R. MCBRIDE
SR. PRODUCTION FOREMAN

1w

CWU338-13PP

CHAPITA WELLS UNIT 338-13
SECTION 13, T9S, R22E NE/SE
UINTAH COUNTY, UTAH
FEDERAL LEASE NO. U-0282



CWU338-13/LW




EXHIBIT "A"
GAS SALES PIPELINE

SCALE: 1" = 2000'
DATE 1-8-92



ENRON OIL & GAS CO.

CWU #338-13
SECTION 13, T9S, R22E, S.L.B.&M.

DRILLING PROGRAM

Date: June 7, 1993

REVISION NO. & DATE: _____

PROSPECT: Chapita Wells Unit LEASE: _____

WELL NAME & NUMBER: Chapita Wells Unit 338-13

WELL CLASSIFICATION: DW-GAS ANTICIPATED PRODUCTION: OIL _____ GAS X OTHER _____

LOCATION CALL: 1983' FSL & 829' FEL (NE SE) (est)
Section 13, T9S, R22E
Uintah County, Utah

ELEVATION: 4940' GL, 4952' KB (estimated)

DIRECTION LIMITATIONS: Maximum deviation for the hole will be 6° w/no more
than a 1°/100' dogleg severity. See page number 4 for distance between
surveys.

TYPE RIG: Land Rotary APPROVED DEPTH: 7000' PERMIT DEPTH: 7000'

CONDUCTOR NEEDED? No If yes, size & how set: _____

CRITERIA FOR DETERMINING CASING SEAT FOR CRITICAL STRINGS: WOC overnight
before cutting off surface casing to weld on head.

CENTRALIZERS (DEPTH & TYPE):

Surface - One 5-10' above shoe & top of first, second & fourth joint.

Production - One @ middle of 1st jt & every third collar to 4500'+.

RECEIVED

JUL 6 1993

DIVISION OF
OIL GAS & MINING

DRILLING PROGRAM

- 2 -

WELL NAME: Chapita Wells Unit 338-13

STAGE COLLARS, BASKETS, OTHER SPECIAL EQUIPMENT:

Surface - Guide shoe
Production - Guide shoe and differential fill float collar with top plug.
Marker joints @ 4000'±.

PUMPING RATES/SPECIAL INSTRUCTIONS: Circulate casing two hours prior to
cementing. Reciprocate casing.

LOGGING PROGRAM: DLL/GR from TD to base of surface casing.
FDC/DSN/GR/caliper from TD to 3100'
Continue caliper to desired top of cement.

CORES: None are anticipated.

SAMPLES: Collect 30' samples from below surface casing to 4300'±. Collect 10'
samples from 4300'± to TD.

FORMATION TESTS: None are anticipated.

MUD LOGGING: (Includes services & depth): From 4300'± to TD.

DETECTION & CONTROL EQUIPMENT: 11" 3000 psig BOP with blind and pipe rams.
11" Annular Preventor. 11" rotating head. Test manifold & BOP's to 3000 psig.
annular preventor to 1500 psig, surface casing to 1500 psig.
Use certified pressure testing service company and leave a copy of the
test chart in the doghouse until rig down.

COMPLETION PROGRAM: To be submitted at a later date.

OTHER SERVICES: None are anticipated.

RECEIVED

JUL 6 8 1993

DIVISION OF
OIL GAS & MINING

WELL NAME: Chapita Wells Unit 338-13FORMATION TOPS & DEPTHS (TENTATIVE)FORMATION NAME & TYPE ESTIMATED DEPTH (EL) DATUM THICKNESS & REMARKS

See attached Prognosis.

X-MAS TREE: 11" 3000# weld on casing head, 7-1/16" 5000# x 11" 3000# tubingspool, 2-1/16" 5000# master valves.MUD PROGRAM

<u>DEPTH INTERVAL</u>	<u>MUD WEIGHT</u>	<u>VIS</u>	<u>WL (cc)</u>	<u>TYPE OF MUD</u>
0' to 240'				Air
240' to 4000'				Air/Mist & Aerated Water
4000' to TD				Aerated 3% KCl water or KCl substitute.
TD	8.5-8.9	38-45	10-15	Gel/polyacrylamide polymer w/5-10% LCM.

DRILLING HAZARDS & SPECIAL INSTRUCTIONS

Lost circulation from 1500' to 3000'±. Underbalanced circulation system will require rotating head. Potential gas kicks in Green River and Wasatch. Potential shale swelling/sloughing problems. Meter air & add foamer to maximize consistency of returns & maintain stable pit levels. Utilize pack off head while running open hole logs. Pre-mix 500-600 bbls mud @ TD as above & displace hole prior to tripping for logs.

WELL NAME: Chapita Wells Unit 338-13

CEMENT PROGRAM

HOLE SIZE	CASING SIZE	DEPTH	CEMENT PROCEDURE
12½"	8 ¾"	240'	Cement w/110 sx Class "G" cement + 2% CaCl ₂ + ½#/sx celloflake. Circulate gelled water ahead of slurry.
7 7/8"	4 ½"	7000'	<p>Cover interval from TD to 4500'± w/50/50 Pozmix + 2% gel + 10% salt. Volume to be calculated from caliper log annular volume to 4500' plus 10% excess.</p> <p>Cover interval from 4500'± to depth specified in conditions of approval with light cement plus specified additives. Volume to be calculated from caliper log annular volume from 4500'± to applicable upper depth plus 5% excess.</p> <p>Circulate casing 2 hrs before cementing. Reciprocate casing during cementing. Pump 10 bbls mud flush ahead of slurry.</p>

CASING PROGRAM

INTERVAL				WEIGHT			MINIMUM SAFETY FACTOR		
SIZE	FROM	TO	LENGTH	#/FT.	GRADE	THREAD	COLLAPSE (psig)	BURST (psig)	TENSILE (psig)
8-5/8"	0'	240'	240'	24.0	J-55	ST&C	1370	2950	263,000
4-1/2"	0'	7000'	7000'	10.5#	J-55	ST&C	4010	4790	146,000

SURVEY SCHEDULE

DEPTH	DISTANCE BETWEEN SURVEYS	MAX DEVIATIONS FROM VERTICAL	MAXIMUM CHANGE DEGREES/100'
0' to 240'	240'	1 degree	1 degree
240' to TD	500' (or as needed)	6 degrees	1 degree

PREPARED BY: Dennis J. BrabecAPPROVED BY: Dennis J. Brabec
Dennis J. Brabec, Division Drilling ManagerAPPROVED BY: C. C. Parsons
C. C. Parsons, Division Drilling Manager


3000 PSIG BOP DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 3000 PSIG RATED.
CASING FLANGE IS 11" 3000PSIG RATED.
BOPE 11" 3000 PSIG

TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 3000 psig.
3. Annular preventor will be tested to 50% of working pressure, 1500 psig.
4. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 3000psig BOPE specifications.


H:\DOC\BOPE\TAH.DIA



ENRON OIL & GAS CO.
LOCATION LAYOUT FOR
CWU #338-13
SECTION 13, T9S, R22E, S.L.B.&M.

NOTE:


Flare Pit is to be located
a min. of 30' from the
Reserve Pit & a min. of
100' from the Well Head.



APPROXIMATE YARDAGES

(6") Topsoil Stripping	= 1,100 Cu. Yds.
Remaining Location	= 4,790 Cu. Yds.
TOTAL CUT	= 5,890 CU.YDS.
FILL	= 3,950 CU.YDS.


EXCESS MATERIAL AFTER 5% COMPACTION	= 1,730 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 1,720 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 10 Cu. Yds.



SCALE: 1" = 50'
DATE: 1-8-92
Drawn By: T.D.H.

X-Section
Scale
1" = 50'


TYP. LOCATION LAYOUT
TYP. CROSS SECTIONS



Elev. Ungraded Ground at Location Stake = 4941.7'

Elev. Graded Ground at Location Stake = 4938.3'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East Vernal, Utah



TOPOGRAPHIC
MAP "A"

DATE 1-8-92



ENRON OIL & GAS CO.


CWU #338-13
SECTION 13, T9S, R22E, S.L.B.&M.



TOPOGRAPHIC
MAP "B"
SCALE: 1" = 2000'
DATE 1-8-92



ENRON OIL & GAS CO.
CWU #338-13
SECTION 13, T9S, R22E, S.L.B.&M.



LEGEND:

- ◊ = Water Wells
- = Abandoned Wells
- ◐ = Temporarily Abandoned Wells
- = Disposal Wells
- = Drilling Wells
- = Producing Wells
- = Shut-in Wells



ENRON OIL & GAS CO.

CWU #338-13
SECTION 13, T9S, R22E, S.L.B.&M.
T O P O M A P " C "

DATE: 1-8-92

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

DATE RECEIVED: 07/08/93

OPERATOR: ENRON OIL AND GAS COMPANY
WELL NAME: CWU 338-13

OPERATOR ACCT NO: N- 0401

API NO. ASSIGNED:

43-047-30434

LEASE TYPE: FED

LEASE NO:

U-0080

LOCATION: NESE 13 - T09S - R22E

UINTAH COUNTY

FIELD: NATURAL BUTTES (630)

FIELD CODE: 630

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond
(Number federal)
☒ Potash (Y/N) ☒
☒ Oil shale (Y/N) ☒
☒ Water permit
(Number 4-1501)
☒ RDCC Review (Y/N) ☒
(Date: _____)

LOCATION AND SITING:

☒ R649-2-3. Unit: Chapita Wells
____ R649-3-2. General.
____ R649-3-3. Exception.
____ Drilling Unit.
____ Board Cause no: _____
____ Date: _____

COMMENTS:

Included in PDD approved 6-11-93

STIPULATIONS:

Uintah assessor



Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

July 12, 1993

Enron Oil & Gas Company
P.O. Box 1815
Vernal, Utah 84078

Gentlemen:

Re: Chapita Wells Unit #338-13 Well, 1983' FSL, 829' FEL, NE SE, Sec. 13, T. 9 S.,
R. 22 E., Uintah County, Utah

Pursuant to Utah Code Ann. § 40-6-18, (1953, as amended), Utah Admin. R. 649-2-3, Application of Rules to Unit Agreements and R. 649-3-4, Permitting of Wells to be Drilled, Deepened or Plugged-Back, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:

1. Compliance with the requirements of Utah Admin. R. 649-1 et seq., Oil and Gas Conservation General Rules.
2. Notification within 24 hours after drilling operations commence.
3. Submittal of Entity Action Form, Form 6, within five working days following commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
4. Submittal of the Report of Water Encountered During Drilling, Form 7.
5. Prompt notification prior to commencing operations, if necessary, to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or R.J. Firth, Associate Director, (Home) (801)571-6068.



Page 2
Enron Oil & Gas Company
Chapita Wells Unit #338-13 Well
July 12, 1993

6. Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring or Venting, if the well is completed for production.

Trash and sanitary waste should be properly contained and transported to approved disposal locations, not retained in or disposed of in pits on location or downhole. Prior to the commencement of drilling operations, the operator should consult the local/county sanitarian and/or the Department of Environmental Quality, Division of Drinking Water/Sanitation, regarding appropriate disposal of sanitary waste.

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-047-32434.

Sincerely,


for R.J. Firth
Associate Director, Oil and Gas

Idc
Enclosures
cc: Bureau of Land Management
 Uintah County Assessor
 J.L. Thompson
WOI1

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/>			5. LEASE DESIGNATION AND SERIAL NO. U-0282
b. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>			6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR ENRON OIL & GAS COMPANY			7. UNIT AGREEMENT NAME CHAPITA WELLS UNIT
3. ADDRESS OF OPERATOR P.O. BOX 1815, VERNAL, UTAH 84078			8. FARM OR LEASE NAME CHAPITA WELLS UNIT
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)* At surface 1983' FSL & 829' FEL NE/SE At proposed prod. zone			9. WELL NO. 338-13
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* 19.4 MILES SOUTHEAST OF OURAY, UTAH			10. FIELD AND POOL, OR WILDCAT CWU/WASATCH
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any) 829' ±			11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SEC. 13, T9S, R22E
16. NO. OF ACRES IN LEASE 2440			12. COUNTY OR PARISH UINTAH
17. NO. OF ACRES ASSIGNED TO THIS WELL 80			13. STATE UTAH
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 1740' ±			19. PROPOSED DEPTH 7000'
20. ROTARY OR CABLE TOOLS ROTARY			21. ELEVATIONS (Show whether DF, RT, GR, etc.) 4938' GRADED GROUND
22. APPROX. DATE WORK WILL START* AUGUST 1993			

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24.0#	240'	125 SX CLASS "G" + 2% CaCl ₂
7 7/8"	4 1/2"	10.5#		+ 1/2 #/SX CELLOFLAKE. 50/50 POZMIX + 2% GEL + 10% SALT TO 400' ABOVE ALL ZONES OF INTEREST (+ 10% EXCESS). LIGHT CEMENT (11 PPG ±) + LCM TO 200' ABOVE OIL SHALE OR FRESH WATER INTERVALS (+ 5% EXCESS).

SEE ATTACHMENTS FOR:

8 POINT PLAN
DRILLING PROGRAM
BOP SCHEMATIC
SURFACE USE AND OPERATING PLAN
LOCATION PLAT
LOCATION LAYOUT
TOPOGRAPHIC MAPS "A", "B", AND "C"
GAS SALES PIPELINE EXHIBIT "A"
WELLSITE SCHEMATIC

DIVISION OF
OIL GAS & MINING

RECEIVED

JUN 24 1993

ENRON OIL & GAS COMPANY WILL BE THE
DESIGNATED OPERATOR OF THE SUBJECT
WELL UNDER NATION WIDE BOND #81307603.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Lynola L. Hall TITLE SR ADMIN. CLERK DATE 6/23/93
(This space for Federal or State office use)

PERMIT NO. APPROVAL DATE
APPROVED BY [Signature] TITLE ASSISTANT DISTRICT
CONDITIONS OF APPROVAL, IF ANY: MANAGER MINERALS DATE AUG 02 1993

U+080-3m-069

NOTICE OF APPROVAL
*See Instructions On Reverse Side

WELL LOCATION INFORMATION

Company/Operator: Enron Oil and Gas Company

API Number 43-047-32434

Well Name & Number: 338-13

Lease Number: U-0282

Location: NESE Sec. 13 T. 9 S. R. 22 E.

Surface Ownership: Federal

Date NOS Received June 7, 1993

Date APD Received June 24, 1993

NOTIFICATION REQUIREMENTS

- | | |
|---------------------------------|--|
| Location Construction | - at least forty-eight (48) hours prior to construction of location and access roads. |
| Location Completion | - prior to moving on the drilling rig. |
| Spud Notice | - at least twenty-four (24) hours prior to spudding the well. |
| Casing String and Cementing | - at least twenty-four (24) hours prior to running casing and cementing all casing strings. |
| BOP and Related Equipment Tests | - at least twenty-four (24) hours prior to initiating pressure tests. |
| First Production Notice | - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days. |

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for a 2M system for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

At a minimum, the surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the usable water zone, identified at \pm 953 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to \pm 753 ft. and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations. Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka	(801) 781-1190
Petroleum Engineer	

Ed Forsman	(801) 789-7077
Petroleum Engineer	

BLM FAX Machine	(801) 789-3634
-----------------	----------------

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

Surface Use Plan of Operations

The reserve pit shall be lined with a plastic nylon reinforced liner. It will be a minimum of 10 mil thickness with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O.

A six-foot berm will be constructed on the east side of the flare pit to help protect personnel working on the location in case of a gas kick.

SURFACE PIPELINE CONDITIONS OF APPROVAL

1. No blading will be allowed on surface pipelines.
2. No pipeline construction will be allowed when soils are muddy and rutting of soils becomes apparent from the use of vehicles. If rutting occurs, operations must cease until soils are dry or frozen.
3. Vehicle use will be restricted to the pipeline route.
4. The Bookcliff Resource Area minerals staff will be notified 24 hours prior to starting construction.
5. All gravel terraces and sandy areas whether wet or dry will be avoided to protect subsurface archaeological resources.
6. All surface lines will be either black or brown in color.
7. Seeding may be required if surface damage is done during the pipeline construction.
8. If any cultural resources are found during construction, all work will stop and the Vernal District BLM office notified.
9. The pipe will be welded on the well location or other areas devoid of vegetation and the pipe dragged along the surface to the connection point with a CAT, backhoe, or grader.
10. The metering of all gas will be done in accordance with On Shore Order No. 5.
11. No construction will be allowed from May 15 to June 20 during the antelope kidding season.

ENRON
OIL & GAS COMPANY

P.O. BOX 1815, VERNAL, UTAH 84078 (801)789-0790

August 27, 1993

RECEIVED

AUG 31 1993

Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

**DIVISION OF
OIL, GAS & MINING**

RE: CHAPITA WELLS UNIT 338-13
SEC. 13, T9S, R22E
UINTAH COUNTY, UTAH
LEASE NO. U-0282


Attn: Ed Forsman:

Dear Mr. Forsman:

Please find attached 3 (three) Sundry Notices proposing to change the surface casing on subject well.

If you have any questions or need additional information, please contact this office.

Very truly yours,
ENRON OIL & GAS COMPANY



George R. McBride
Sr. Production Foreman

cc: Division of Oil Gas & Mining
Curt Parsons
Doug Weaver/Toni Miller
Diane Cross - Houston EB-2370
File

/lwSundry

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

5. Lease Designation and Serial No.

U-0282

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

CHAPITA WELLS UNIT

8. Well Name and No.

CWU 338-13

9. API Well No.

43-047-32434

10. Field and Pool, or Exploratory Area

CWU/WASATCH

11. County or Parish, State

UINTAH, UTAH

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

ENRON OIL & GAS COMPANY

3. Address and Telephone No.

P.O. BOX 1815, VERNAL, UTAH 84078 (801) 789-0790

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1983' FSL & 829' FEL NE/SE
SEC. 13, T9S, R22E

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other


- ☒ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Enron Oil & Gas Company proposes to change the surface casing on the subject well from 8 5/8' 24.0# J-55 STC 1370 PSI 2950 PSI 263,000# to:

9 5/8" 36.0# J-55 STC 2020 PSI 3520 PSI 423,000#



ACCEPTED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: 8-31-93
BY: [Signature]

14. I hereby certify that the foregoing is true and correct

Signed

[Signature]

Title Sr. Admin. Clerk

Date 8/27/93

(This space for Federal or State office use)

Approved by

Conditions of approval, if any:

Title

Date

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: ENRON 43-047-32434

WELL NAME: CHAPITA WELLS UNIT 338-13

Section 13 Township 9S Range 22E County UINTAH

Drilling Contractor CHANDLER

Rig # 1

SPUDDED: Date 9/17/93

Time 11:00 AM

How DRY HOLE

Drilling will commence _____

Reported by ED TROTTER

Telephone # 1-789-0990

Date 9/17/93 SIGNED FRM

RECEIVED

OCT 06 1993

OPERATOR ENRON OIL & GAS COMPANYADDRESS P.O. Box 1815VERNAL, UTAH 84078OPERATOR ACCT. NO. N 0401

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	DIVISION OF OIL, GAS & MINING	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	04905	→	43-047-32434	CHAPITA WELLS UNIT 338-13	NESE	13	9S	22E	UINTAH	9/17/93	9/17/93
WELL 1 COMMENTS: Entity added 10-14-93. Jec											
2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

Linda L. Wall
Signature
Sr. Admin. Clerk 10/4/93
Title Date
Phone No. 801 , 789-0790

ENRON

Oil & Gas Company

P.O. Box 250 Big Piney, Wyoming 83113 (307) 278-3331

October 8, 1993

Mr. Ed Forsman
Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078


RE: WATER ENCOUNTERED
CHAPITA WELLS UNIT 338-13
LEASE: U-0282
SEC. 13, T9S, R22E
UNITAH COUNTY, UTAH

Dear Mr. Forsman:

Please find attached a Sundry Notice of water encountered while drilling the subject well.

If further information is required, please contact this office.

Sincerely,


C.C. Parsons
Division Operations Manager

kt

cc: Utah Board of Oil, Gas and Mining
D. Weaver
T. Miller
Vernal Office
File

ENRON
Oil & Gas Company

P.O. Box 250 Big Piney, Wyoming 83113 (307) 276-3331

October 25, 1993

RECEIVED

OCT 28 1993

Mr. Ed Forsman
Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

DIVISION OF
OIL, GAS & MINING

RE: SPUDDING
CHAPITA WELLS UNIT 338-13
LEASE: U-0282
SEC. 13, T9S, R22E
UNITAH COUNTY, UTAH

Dear Mr. Forsman:

Please find attached a Sundry Notice for the spudding of the subject well.

If further information is required, please contact this office.

Sincerely,



C.C. Parsons
Division Operations Manager

kt

cc: Utah Board of Oil, Gas and Mining
D. Weaver
T. Miller
Vernal Office
File

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICE AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT ---" for such proposals"

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	5. Lease Designation and Serial No. U 0282
2. Name of Operator ENRON OIL & GAS COMPANY	6. If Indian, Allottee or Tribe Name
3. Address and Telephone No. P.O. BOX 250, BIG PINEY, WY 83113 (307) 276-3331	7. If Unit or C.A., Agreement Designation CHAPITA WELLS UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 1983' FSL - 829' FEL NE/SE SECTION 13, T9S, R22E	8. Well Name and No. CHAPITA WELLS UNIT 338-13
	9. API Well No. 43-047-32434
	10. Field and Pool or Exploratory Area CWU/WASATCH
	11. COUNTY STATE UINTAH UTAH


12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT	<input type="checkbox"/> ABANDONMENT	<input type="checkbox"/> CHANGE OF PLANS
<input checked="" type="checkbox"/> SUBSEQUENT REPORT	<input type="checkbox"/> RECOMPLETION	<input type="checkbox"/> NEW CONSTRUCTION
<input type="checkbox"/> FINAL ABANDONMENT NOTICE	<input type="checkbox"/> PLUGGING BACK	<input type="checkbox"/> NON-ROUTINE FRACTURING
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> ALTERING CASING	<input type="checkbox"/> CONVERSION TO INJECTION
	<input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> WATER ENCOUNTERED

(Note: Report results of multiple completion on Well Completions or Recompletion Report and Log Form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details and give pertinent dates, including estimated date of starting any proposed work if well is directionally drilled give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work).

Water was encountered while drilling the subject well at depths from 1751' to 4802' KB in the Green River formation. Please find attached a copy of the Report of Water Encountered During Drilling (Form 7).



14. I hereby certify that the foregoing is true and correct.

SIGNED Hendac Lannoy TITLE Engineering Clerk DATE 10/08/93

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

REPORT OF WATER ENCOUNTERED DURING DRILLING - FORM 7 (1/89)

1. Well name and number: CHAPITA WELLS UNIT 338-13
API number: 43-047-32434

2. Well location: QQ SENE section 13 township 9S range 22E county Uintah

3. Well operator: Eaton Oil & Gas Company
Address: P.O. Box 230 phone: (307) 276-3331
Big Piney, Wyoming 83113

4. Drilling contractor: CHANDLER DRILLING CORPORATION
Address: 555 17th Street, Suite 1850 phone: (303) 295-0400
Denver, CO 80202

5. Water encountered (continue on reverse side if necessary)

Depth		Volume (flow rate or head)	Quality (fresh or salty)
from	to		
1810'		Est. 80 - 100 BPPH	Slightly Salty

6. Formation tops: GreenRiver Oil Shale 1751'
Wasatch Peters Point 4802'


If any analysis has been made of the water encountered, please attach a copy of the report to this form.

I certify that this report is true and complete to the best of my knowledge.

Name Leo R. Schueler
Title Drilling Consultant

Signature Leo R. Schueler
Date 10/4/93

Comments:



ENRON

Oil & Gas Company

P.O. Box 250 Big Piney, Wyoming 83113 (307) 276-3331

October 25, 1993

Mr. Ed Forsman
Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

RECEIVED

OCT 28 1993

DIVISION OF
OIL, GAS & MINING

RE: SPUDDING
CHAPITA WELLS UNIT 338-13
LEASE: U-0282
SEC. 13, T9S, R22E
UNITAH COUNTY, UTAH

Dear Mr. Forsman:

Please find attached a Sundry Notice for the spudding of the subject well.

If further information is required, please contact this office.

Sincerely,



C.C. Parsons
Division Operations Manager

kt

cc: Utah Board of Oil, Gas and Mining
D. Weaver
T. Miller
Vernal Office
File

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICE AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

Use "APPLICATION FOR PERMIT -" for such proposals"

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

ENRON OIL & GAS COMPANY

3. Address and Telephone No.

P.O. BOX 250, BIG PINEY, WY 83113 (307) 276-3331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1983' FSL - 829' FEL NE/SE

SECTION 13, T9S, R22E

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ NOTICE OF INTENT
☒ SUBSEQUENT REPORT
☐ FINAL ABANDONMENT NOTICE

TYPE OF ACTION

☐ ABANDONMENT ☐ CHANGE OF PLANS
☐ RECOMPLETION ☐ NEW CONSTRUCTION
☐ PLUGGING BACK ☐ NON-ROUTINE FRACTURING
☐ CASING REPAIR ☐ WATER SHUT-OFF
☐ ALTERING CASING ☐ CONVERSION TO INJECTION
☒ OTHER SPUDDING

(Note: Report results of multiple completion on Well Completions
or Recompletion Report and Log Form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details and give pertinent dates, including estimated date of starting any proposed work if well is directionally drilled give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work).

Enron Oil & Gas Company spudded a 12-1/4" surface hole at the subject location at 11:00 am, 9/17/93.
The contractor was Leon Ross Drilling & Construction, Inc. Ed Forsman of the BLM District
and Frank Mathews of the UOGM were notified of the spud on 9/17/93.

FORM APPROVED

Budget Bureau No. 1004-0135

Expires September 30, 1990

5. Lease Designation and Serial No.

U-0282

6. If Indian, Allottee or Tribe Name

7. If Unit or C.A., Agreement Designation

CHAPITA WELLS UNIT

8. Well Name and No.

CHAPITA WELLS UNIT 338-13

9. API Well No.

43-47-32434

10. Field and Pool or Exploratory Area

CHAPITA WELLS/WASATCH

11. COUNTY STATE

UINTAH UTAH

14. I hereby certify that the foregoing is true and correct.

SIGNED Genda Cranny

TITLE Engineering Clerk

DATE

10/25/93

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

OCT 28 1993

DIVISION OF
OIL, GAS & MINING

ENRON
Oil & Gas Company

P.O. Box 250 Big Piney, Wyoming 83113 (307) 276-3331

NOV 15 1993

DIVISION OF
OIL, GAS & MINING

November 10, 1993

Mr. Ed Forsman
Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078


RE: PLUGGING & ABANDONMENT
CHAPITA WELLS UNIT 338-13
LEASE: U-0282
SEC. 13, T9S, R22E
UNITAH COUNTY, UTAH

Dear Mr. Forsman:

Please find attached a Sundry Notice of the plugging and abandonmetn of the subject well.

If further information is required, please contact this office.

Sincerely,


C.C. Parsons
Division Operations Manager

kt

cc: ~~Utah Board of Oil, Gas and Mining~~
D. Weaver
T. Miller
Vernal Office
File

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires September 30, 1990

SUNDRY NOTICE AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

Use "APPLICATION FOR PERMIT --" for such proposals"

SUBMIT IN TRIPLICATE

NOV 15 1993

DIVISION OF
OIL, GAS & MINING

5. Lease Designation and Serial No.

U-0282

6. If Indian, Allottee or Tribe Name

7. If Permit or C.A., Agreement Designation

CHAPITA WELLS UNIT

8. Well Name and No.

338-13

9. API Well No.

43-047-32434

10. Field and Pool or Exploratory Area

CWU/WASATCH

11. COUNTY STATE

UINTAH UTAH

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

- ☐ NOTICE OF INTENT
☒ SUBSEQUENT REPORT
☐ FINAL ABANDONMENT NOTICE

- ☒ ABANDONMENT
☐ RECOMPLETION
☐ PLUGGING BACK
☐ CASING REPAIR
☐ ALTERING CASING
☐ OTHER
☐ CHANGE OF PLANS
☐ NEW CONSTRUCTION
☐ NON-ROUTINE FRACTURING
☐ WATER SHUT-OFF
☐ CONVERSION TO INJECTION

(Note: Report results of multiple completion on Well Completions
or Recompletion Report and Log Form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details and give pertinent dates, including estimated date of starting any proposed work if well is directionally drilled give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work).

Enron Oil & Gas Company plugged and abandoned the subject well as follows:

1. Placed Plug #1 @ 5398-2000'.
2. Placed Plug #2 @ 2730-2440'.
3. Placed Plug #3 @ 1383-1180'.
4. Placed Plug #4 @ 278-187'.
5. Placed Plug #5 @ 50' to surface.
6. Dry hole marker installed 10/18/93.

14. I hereby certify that the foregoing is true and correct.

SIGNED Kenda C. C. [Signature] TITLE Engineering Clerk DATE 11/11/93

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

ENRON

Oil & Gas Company

P.O. Box 250 Big Piney, Wyoming 83113 (307) 276-3331

November 10, 1993

NOV 15 1993

Mr. Ed Forsman
Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

DIVISION OF
OIL, GAS & MINING


RE: COMPLETION REPORT
CHAPITA WELLS UNIT 338-13
LEASE: U-0282
SEC. 13, T9S, R22E
UNITAH COUNTY, UTAH

Dear Mr. Forsman:

Please find attached a Completion Report for the subject well.

If further information is required, please contact this office.

Sincerely,


C.C. Parsons
Division Operations Manager

kt

cc: Utah Board of Oil, Gas and Mining
D. Weaver
T. Miller
Vernal Office
File

UNITED STATES

DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT

NOV 15 1993

DIVISION OF

OIL, GAS & MINING

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

5. LEASE DESIGNATION AND SERIAL NO.

U-0282

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

CHAPITA WELLS UNIT

8. FORM OR LEASE NAME

CHAPITA WELLS UNIT

1. TYPE OF WELL

OIL WELL ☐ GAS WELL ☒ DRY ☐ OTHER ☐

2. TYPE OF COMPLETION:

NEW WELL ☒ WORK OVER ☐ DEEPEN ☐ PLUG BACK ☐ DIFF. RES. ☐ OTHER ☐

3. NAME OF OPERATOR

ENRON OIL & GAS COMPANY

4. ADDRESS OF OPERATOR

P.O. BOX 250 BIG PINEY, WYOMING 83113

5. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*

At surface 1983' FSL - 829' FEL NE/SE

At top prod. interval reported below

At total depth

15. DATE SPUDDED

9/17/93

16. DATE T.D. REACHED

10/11/93

17. DATE COMPL. (Ready to prod.)

P & A'd

18. ELEVATIONS (DP, RES. RT. OR, ETC.)*

4949' KB

19. ELEV. CASINGHEAD

4938' PGL

20. TOTAL DEPTH, MD & TVD

7017' KB

21. PLUG BACK T.D., MD & TVD

22. IF MULTIPLE COMPLETIONS, HOW MANY?

23. ROTARY TOOLS

ROTARY

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION-TOP, BOTTOM, NAME (MD AND TVD)*

P & A'd

25. WAS DIRECTIONAL SURVEY MADE?

26. TYPE ELECTRIC AND OTHER LOGS RUN

DLL/FDC/DSN/GR-CALIPER 11-3-93

27. WAS WELL CORED?

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
9-5/8"	36.0 #, J-55	236' KB	12-1/4"	125 SX CLASS "G"	NONE

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT	SCREEN (MD)

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)

31. PERFORATION RECORD (Interval, size and number)

P & A'd

32. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED

33.* PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping, size and type of pump)				WELL STATUS (Flowing or shut-in)	
P & A'd		P & A'd				P & A'd	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR	OIL-BBL.	GAS-MCF.	WATER-BBL.	GAS-OIL RATIO
P & A'd			TEST PERIOD				
FLOW, TUBING PRESS.	CASING PRESSURE		CALCULATED	OIL-BBL.	GAS-MCF.	WATER-BBL.	OIL GRAVITY-API (CORR.)
			24-HOUR RATE				

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

N/A

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

NONE

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

SIGNED

Ardena C. Tanna

TITLE ENGINEERING CLERK

DATE

11/10/93

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

Items 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: Sacks Ce Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

PRIVACY ACT

The Privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et. seq., 25 U.S.C. et. seq., 43 CFR 3160

PRINCIPLE PURPOSE: The information is to be used to evaluate the actual operations performed in the drilling or an oil or gas well on a Federal or Indian lease.

ROUTINE USES: (1) Evaluate the equipment and procedures used during the drilling of the well. (2) The review of geologic zones and formation encountered during drilling. (3) Analyze future applications to drill in light of data obtained and methods used. (4)(5) Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this report and disclosure of its information is mandatory once an oil or gas well is drilled.

The Paperwork Reduction Act of 1980 (44 U.S.C. 3501, et. seq.) requires us to inform you that:

This information is being collected to allow evaluation of the technical, safety, and environmental factors involved with drilling and producing oil and gas on Federal and Indian oil and gas leases.

This information will be used to analyze operations and compare equipment and procedures actually used with the proposals applied for.

Response to this request is mandatory once an oil or gas well is drilled.

SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):

38.

GEOLOGIC MARKERS

				TOP		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	MEAS. DEPTH	TRUE VERT. DEPTH
			GREEN RIVER BEND			
			BASE M MARKER		4442'	
			N LIMESTONE		4644'	
			WATAATCH			
			PETER'S POINT		4788'	
			CHAPITA WELLS		5318'	
			BUCK CANYON		5878'	
			ISLAND		6801'	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator
EOG Resources, Inc.

3a. Address
600 17th Street, Suite 1000N, Denver, CO 80202

3b. Phone No. (include area code)
303-824-5526

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**1983' FSL & 829' FEL (NE/SE)
Sec. 13-T9S-R22E 40.03418 LAT 109.38128 LON**

5. Lease Serial No.

U-0282

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

Chapita Wells Unit

8. Well Name and No.

Chapita Wells Unit 338-13

9. API Well No.

43-047-32434

10. Field and Pool, or Exploratory Area

Natural Buttes/Wasatch

11. County or Parish, State

Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION				
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off	
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity	
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Marker plate placed	
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon		
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal		

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Dry hole marker was replaced with marker plate 4' below ground level on 8/22/2006.

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Mary A. Maestas

Title **Regulatory Assistant**

Signature

Mary A. Maestas

Date

08/23/2006

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

AUG 25 2006

DIV. OF OIL, GAS & MINING